



Project	Downtown Extension	Sunnydale Sewer	Muni Metro Turnback	Laguna Honda
Symbol	●	●	●	●
Number of Tests, N	118	83	62	32
Mean, $\mu$ , blows/ft	11.3	12.5	14.7	14.8
Standard Deviation, $\sigma$ , blows/ft	8.4	9.4	9.1	8.0

FIG\_15: Statistical Summary of SPT N Values for Fill